BRUHATH BANGALORE MAHANAGARA PALIKE
SCHEDULE B

Name of Works : Providing Gallery to Musical Fountain in JP Park in Ward No 17, J P Park.

Sl	Description of Item	Unit	Schedule B		
			Qty	Rate	Amount
1	2	3	4	5	6
1	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications.	Cum	1126.05	226.00	254486.85
2	KSRB 2.8 : Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift, complete as per specifications,	Cum	104.91	2806.00	294377.46
3	KSRB 4-1.2 : Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM curing complete as per specifications.	Cum	108.10	6283.00	679192.30
4	Above 125 %	Cum	40.98	6273.14	257048.21
5	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications. TMT bars Fe 550	Tonne	55.81	90769.00	5066044.81
6	Above 125 %	Tonne	52.29	97667.05	5107085.97
7	Earth work for lowering and levelling the ground other than foundation works by mechanical means upto 3.00 depth, including providing shoring strutting and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, filling back the excavated earth to the extent required & utilising/transporting the remaining earth upto 1.00 km lead. Including the cost of labour & HOM as per drawing and technical specification.. (item 2.24 P.W.D. SR-2018-19)	Cum	186.00	69.00	12834.50
8	KSRB 4.2.7 : Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintles and beams retaining walls, return walls, walls (any thickness) including attached pilasters, columns, ,pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6. (Issue rate as on date 02-21-2021, Item No. 4.12)	Cum	617.73	7848.33	4848175.23
9	KSRB 4-6.1 : Providing and removing a centering, shuttering, strutting, propping etc., and removal of form work for a foundation footing bases of column for mass concrete including cost of all materials, labours, complete as per specificatons (Pg No 16-Item No 4.28@ P.W.D SR -2018-19)	Cum	243.84	291.85	71164.10

Scanned with CamScanner

10	KSRB 4-6.5: Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square /rectangular / polygon in plan including cost of all materials, labour complete as per specification. Specification No. KBS 4.6.2 (P.No.16, I.No.4.32 of P,W, D S.R 2018-19)	Cum	591.12	515.82	304913.62
11	KSRB 4-6.7: Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for sides and soffits of beams, beam haunchings, cantilever, girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (P.No.17, I.No.4.34 of PWD S.R 2018-19)	Cum	369.12	330.31	121923.31
12	KSRB 4-6.3 : Providing and removing centering, shuttering, strutting, propping etc., and removal form work for flat surface such as suspended floors, roofs, landings, balconies and like, thickness upto 200mm including cost of materials, labhour complete as per specification.(P.No.16,I.No.4.29.2)	Cum	256.50	452.48	116060.30
13	KSRB 4-6.11 :Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials, labour complete as per specificaiton. Specification No. KBS 4.6.2.(I.No.4.38)	Cum	544.16	588.22	320085.71
	Sub Total				**17453392.38**

EXECUTIVE ENGINEER
RR Nagar Division

Scanned with CamScanner